

Item	Description	Unit	Quantity	Unit Price	Amount
A.	5th Ave and 6th Street – Local Curb, Gutter and Sidewalk Works				
.1	Existing Concrete Curb Removal and Disposal	lin.m.	240	\$	\$
.2	Asphalt Milling (Gutter) (25 mm Depth Average 500mm width)	lin.m.	240	\$	\$
.3	150 mm Subgrade Preparation (Required Below Sidewalk and Driveway Access)	sq.m.	175	\$	\$
.4	Monolithic Rolled Curb, Gutter, and 1200 mm Sidewalk (incl. 50 mm Leveling Course)	lin.m.	75	\$	\$
.5	Vertical Curb and Gutter (Incl. 50 mm Leveling Course and Curb Depression where indicated)	lin.m.	165	\$	\$
.6	Vertical Curb and Sidewalk Crossing Monolithic (incl. 50 mm Leveling Course) <i>Exact Location to be finalized prior to construction</i>	Each	2	\$	\$
.7	Vertical Curb and Separate Sidewalk Access (incl. 50 mm Leveling Course) <i>Exact Location to be finalized prior to construction</i>	Each	2	\$	\$
.8	Reconfigure Accessible Stall to Driveway Access	Lump Sum	1	\$	\$
.9	Tie-In to Existing Vertical Curb	Each	2	\$	\$
.10	Tie-In to Existing Sidewalk	Each	1	\$	\$
.11	Concrete Wheelchair Ramp – Type A	Each	1	\$	\$
.12	Material Testing	Cash Allowance	1	\$5,000.00	\$5,000.00
.13	Common Excavation	cu.m.	5	\$	\$
.14	Topsoil Removal, Replacement, and Seeding	sq.m.	75	\$	\$
.15	Catch Basin Adjustment	Each	1	\$	\$
				Sub-Total	\$

Item	Description	Unit	Quantity	Unit Price	Amount
B.	3rd Ave East (100 Block)				
.1	Existing Concrete Curb Removal and Disposal	lin.m.	180	\$	\$
.2	Concrete Apron Removal and Replacement (Including 50mm Leveling Course)	Each	5	\$	\$
.3	Concrete Apron Removal and Replacement with Concrete Wheelchair Ramp (Seniors Center)	Each	1	\$	\$
.4	Install Vertical Curb and Gutter (Including 50mm Leveling Course)	lin.m.	180	\$	\$
.5	Pavement Sawcut, Removal and Disposal *(If Needed)	sq.m	25	\$	\$
.6	Asphalt Milling (Gutter) (25 mm Depth Average, 1m Width)	lin.m.	340	\$	\$
.7	Hot Mix Asphalt Pavement Resurface Including Tack and Fog Coats (50 mm Deep)	sq.m.	2150	\$	\$
.8	Asphalt Leveling Course *(If Needed)	Tonne	25	\$	\$
.9	Adjustment of Appurtenances (1 - Manhole, 1 - Catch Basin)	Each	2	\$	\$
.10	Topsoil Removal Replacement and Seeding	sq.m.	180	\$	\$
.10	Material Testing	Cash Allowance	1	\$5,000.00	\$5,000.00
				Sub-Total	\$

Item	Description	Unit	Quantity	Unit Price	Amount
C.	Misc. Concrete & Asphalt – <i>Provide a unit price and quantity for budgeted amount.</i>				
.1	Surface Asphalt Patching	sq.m			\$140,000.00
.2	Deep Asphalt Patching	sq.m			\$25,000.00
.3	Misc. Concrete Sidewalk Replacement	lin.m.			\$10,000.00
.4	Misc. Concrete Curb Replacement	lin.m.			\$10,000.00
.5	Aquatic Center Entrance Widening (16m Mono Walk Replacement, 50m ² - 50mm Asphalt c/w 150mm base)	Lump Sum	1	\$	\$
				Sub-Total	\$

BID FORM SUMMARY

Item	Location	Description	Amount
A.	5 th Ave and 6 th Street – Local Curb, Gutter and Sidewalk Works	Concrete	\$
B.	3 rd Ave East (100 Block)	Resurface/Concrete	\$
C.	Misc. Concrete & Asphalt	Patching/Concrete	\$
Subtotal			\$
GST 5%			\$
PST 6%			\$
Total			\$

Estimated Bid Price: _____

_____ / 100 dollars in Canadian funds

SCHEDULE "A"

**2024 INFRASTRUCTURE UPGRADE INVITATION TO TENDER
Bid Form**

Name of Company: _____

Name of Owner: _____

Location of Head Office: _____

Business Start Date: _____

Phone Number: _____

Email Address: _____

Number of Employees: _____

Designated Staff Contact Person: _____

Equipment:

List 2 similar completed projects similar in scope:

1. _____

2. _____

List 2 references: Please provide name and phone number

1. _____

2. _____

